

Schedule of Quantities

10

Estimated Cost	: R s 2, 43, 132/-
Earnest Money	: 2 %
Time	: 30 days

NAME OF WORK:- RM and upkeep of 'ITPO' Premises at Pragati Maidan during 2008-09

SH.: Renovation of toilet At G.F Admn.Bldg

S.No	Description of items	Qty.	Rate	Unit	Amount
1	P/f water closet squatting pan (Indian type W.C pan) with 100 mm sand cat iron P or S trap, 10 liter low level white P.V.C flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, Parryware/Handware/Seabird/Orient (Coral) with all fittings and fixtures complete i/c cutting and making good the walls and floors wherever required. a)White Vitreous china Orrisa pattern W.C. pan of size 580-x 440 mm with integral footrests.	1 Nos		Each	
2	P/f white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 liter low level white P.V.C flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, Parryware/Handware/Seabird/Orient (Coral) with all fittings and fixtures complete i/c cutting and making good the walls and floors wherever required. a)W.C. pan with ISI marked white solid plastic seat and lid.	2 Nos		Each	
3	P/f white vitreous china flat back half stall urinal of 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size CP brass flush pipe, spreaders with unions and clamps (all in CP brass) with waste fittings as per IS: 2556, CI trap				



	with outlet grating and other couplings in CP brass i/c painting of fittings and cutting and making good the walls and floors wherever required. a) Range of Three half stall urinal with 10 liter PVC automatic flushing cistern	1 set		Each	
4	P/F coloured vitreous china wash basin (of existing pattern in Toilet of admn; bldg 1 st floor.) with C.I./M.S. brackets 15mm C.P. brass pillar taps (heavy duty), 32mm C.P. brass waste of standard pattern, i/c painting of fitting and brackets, cutting and making good the walls wherever required as per the direction of Engineer-in charge. a) coloured wash basin (570x450mm oval shape) cera or eq. make with single 15mm C.P. brass pillar cock of Parko or Eq. make.	4 Nos		Each	
5	Providing and laying in position cement concrete of specified grade ex/c the cost of centering and shuttering--All work up to plinth level. b) 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) b) 1:5:10 (1 cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size)	2.00 cum 3.00 cum		Cum Cum	
6	R.C.C work in beams, suspended floors, roofs having slope up to 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level ex/c the cost of c/s, finishing and reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size.)	0.50 cum		Cum	
7	Centering and shuttering including strutting, propping etc. and removal of form for: a) Suspended floors, roofs, landings, balconies and access platform.	3.00		Sqm	
8	Reinforcement for R.C.C work in/c straightening, cutting,				