

Tender Inviting Authority: M(RB)

Name of Work:- Demolition/Dismantling of Hall number 7 (Block A-H) and adjoining buildings namely CMD Building, Security Building and adjoining landscaped areas inside Bharat Mandapam premises, including removal of all malba and debris from the demolished/dismantled site, levelling the siteand handing over the clear site.

Contract No:

Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NOTE:-

- The rates should be quoted exclusive of GST as applicable
- The agency should file ECR against ESI & EPF for the individual workers engaged in ITPO & submit the same with bank certified copy, bill, wage sheet & attendance sheet etc. before payment.
- Contractural Labour Act Registration if applicable.
- The quoted price is the one which is to be paid to ITPO.
- Detailed valuation annexures are attached with Tender documents.
- Blasting prohibited

NUMB	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4.00	5	6.00	54	55
1.00	Demolishing and Dismantling of Hall number 7 (Block A-H) andincluding all doors, windows, sanitary and water supply fittings and fixtures, internal electrical installations, electrical mains, DBs, street light poles up to the ground level including demolishing of brick masonry work / rubble stone masonry work, PCC & RCC work either manually or by mechanical means including disposal of serviceable and unserviceable materials after the demolishing for all leads and lifts as per the direction of Engineer in charge. This Work also includes demolishing of Terrace water tanks, parapets, staircase head rooms, with fittings etc., all complete as per the direction of Engineer In Charge a). Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading for all leads including all lifts involved to approved municipal dumping ground or recycling units as approved by the Engineer-in-charge. Arranging for termination of all utilities including water supply, electricity, sewage before commencement of demolition. All the serviceable & unserviceable materials such as steel, Bricks, rubblestone, doors, windows etc., obtained from the building belongs to the agency and should be taken away by the agency from the vicinity of the site. Department will not have any lien on any dismantled material. All roads and open areas adjacent to the work site shall either be closed or suitably protected during the demolition process. All practical steps shall be taken to prevent danger to persons employed from risk or fire or explosion, or flooding and no floors, roof, or other part of a building shall be so overloaded with debris or materials as to render unsafe. No processing charges paid by the contractor to the C&D waste plant shall be reimbursed to the contractor.	8066.96	sqm.	1153.60	9306045.06	INR Ninety Three Lakh Six Thousand &Forty Five and Paise Six Only

2.00	Demolishing and Dismantling of Hall number 7 adjoining buildings namely CMD building and Security building and including all doors, windows, sanitary and water supply fittings and fixtures, internal electrical installations, electrical mains, DBs, street light poles up to the ground level including demolishing of brick masonry work / rubble stone masonry work, PCC & RCC work either manually or by mechanical means including disposal of serviceable and unserviceable materials after the demolishing for all leads and lifts as per the direction of Engineer in charge. This Work also includes demolishing of Terrace water tanks, parapets, staircase head rooms, with fittings etc., all complete as per the direction of Engineer In Charge a). Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading for all leads including all lifts involved to approved municipal dumping ground or recycling units as approved by the Engineer-in-charge. Arranging for termination of all utilities including water supply, electricity, sewage before commencement of demolition. All the serviceable & unserviceable materials such as steel, Bricks, rubblestone, doors, windows etc., obtained from the building belongs to the agency and should be taken away by the agency from the vicinity of the site. Department will not have any lien on any dismantled material. All roads and open areas adjacent to the work site shall either be closed or suitably protected during the demolition process. All practical steps shall be taken to prevent danger to persons employed from risk of fire or explosion or flooding and no floors, roof or	1820.01	sqm.	983.46	1789907.00	INR Seventeen Lakh Eighty Nine Thousand Nine Hundred & Seven Only
13.00	Note: The rates should be quoted inclusive of GST as applicable					
Total in Figures					11095952.00	INR One Crore Ten Lakh Ninety Five Thousand Nine Hundred & Fifty Two Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				